

FORM 30, PFE
PACIFIC FRUIT EXPRESS COMPANY
WORK ORDER AUTHORITY

8-1-44-2M

Office of Asst. Gen. Mgr., E.&R.
San Francisco, Calif., Dec. 9, 19 44
(Place) (Date)

General Manager's No. 0-681
Ass't Gen'l Mgr's No. E&R-1412
No. _____

Authority for Expenditure of \$ 5554.00 is requested for purpose of erecting temporary
boarding house facilities to property at Tucson, Arizona.
(Station or Location)

Description of project:


Construct 20' x 35' temporary boarding house and lunchstand.

Recommendations:

Local labor supply is exhausted, necessitating importing Mexican Nationals to supplement our limited crews. There are no boarding house facilities at this location and at present men are transported by truck to eating establishments in town, a distance of about 1-1/2 miles. This method takes the men away from the plant and they are not available for icing operations if needed. This situation has caused train delays in the past, resulting in criticism which can be overcome only by feeding men on the premises or doubling the present crew and staggering meal periods.

Proposed boarding house will also allow for better control over the men as there will not be the need for them to go into town which often results in their not returning for work when their services are urgently required.

As this facility will not be required after the duration it is properly chargeable to operating as shown.



(Included in 1945 Budget.)

DISTRIBUTION OF ESTIMATE

Investment in physical property	\$
Less—Ledger value of property retired.....	\$
Less—Cost at current prices of new parts of the kind retired.....	\$
Net—investment in physical property.....	\$
Operating Expenses <u>IMP Acct. 58 - Tucson</u>	\$ <u>5554.00</u>
Accrued depreciation.....	\$
Material and supplies	\$
<u>Material in temporary tracks, structures, etc.</u>	<u>500.00</u>
Estimated cost of project	<u>6054.00</u>
Less donations, grants, or proportion payable by	\$ <u>500.00</u>
Cost to Pacific Fruit Express Company	\$ <u>5554.00</u>

Submitted by H. W. Barrett, Plant Manager

Recommended by N. J. White AGM-E&R

Calculations and distribution correct:

Recommended by _____

Approved: [Signature]
Vice-President and General Manager

Date 12-13- 19 44

Date DEC 22 '44, 19 _____

PACIFIC FRUIT EXPRESS COMPANY
RECEIVED
DEC 12 1944
OFFICE OF MONITOR

PACIFIC FRUIT EXPRESS COMPANY
RECEIVED
DEC 22 1944
OFFICE OF AUDITOR

PACIFIC FRUIT EXPRESS COMPANY

SHEET 1 OF 2 SHEETS

WORK ORDER AUTHORITY—Detail of Estimated Expenditures

San Francisco, California.

Engr. & Refrig. DEPARTMENT

December 9, 1944

LOCATION: Tucson, Arizona

DESCRIPTION: Construct 20' x 35' temporary boarding house and lunch stand.

GENERAL MANAGER'S No. 0-681

DEPARTMENT No. E&R-1412

DESCRIPTION	QUANTITY	UNIT	UNIT COST		LABOR	MATERIAL OR TRANSPORTATION CHARGES	TOTAL CHARGEABLE TO	
			LABOR	MATL.			INVESTMENT ACCOUNT	OPERATING EXPENSES
<u>ACCT. 58 - MAINTENANCE ICING PLATFORM & MACHINERY.</u>								
Sewer water & gas lines	Est.				150.00	200.00		
Electric line	"				50.00	50.00		
Earthwork	30	yd	2.00		60.00			
Concrete	15	"	12.00	12.00	180.00	180.00		
Wire fabric	7	c sq f	1.00	3.00	7.00	21.00		
Brickwork	12	M	60.00	40.00	720.00	480.00		
Flues	Est.				75.00	75.00		
Steel	.5	ton	50.00	200.00	25.00	100.00		
Miscl. iron	5	cwt	2.00	10.00	10.00	50.00		
Bolts	1	"		6.00		6.00		
Nails	2	"		6.00		12.00		
Screws	.2	"		35.00		7.00		
Lumber framing	2	M	75.00	75.00	150.00	150.00		
" sheathing	1.5	"	80.00	80.00	120.00	120.00		
Millwork	Est	"			75.00	150.00		
Roofing	12	"	3.00	6.00	36.00	72.00		
Paint	10	gal	3.00	3.00	30.00	30.00		
Plumbing	Est				150.00	200.00		
Hardware	"				15.00	50.00		
Lights	6	ea	10.00	6.00	60.00	36.00		
Miscl. equip.	Est					750.00		
Sales tax	2	1%				54.78		
M.S.E.	7	1%				195.56		
Contingencies	10	1%			191.00	298.66		
Total					2104.00	3288.00		5392.00

(Continued)

WORK ORDER AUTHORITY--Detail of Estimated Expenditures

San Francisco, California.

December 9, 1944

0-681

1412-1412

Construction of 20' x 25' temporary boarding house and lunch stand.

Tucson, Arizona

Eng. & Electric.

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT	LABOR	MATERIAL OR TRANSPORTATION CHARGE	TOTAL CHARGEABLE TO INVESTMENT ACCOUNT	OPERATING EXPENSES
Gutter water & gas lines Est.						150.00	200.00	
Electric line						50.00	50.00	
Earthwork	30	yd	2.00	60.00				
Concrete	15	"	12.00	180.00				
Wire fabric	7	sq ft	1.00	7.00				
Brickwork	12	M	40.00	480.00				
Plum	Est.			75.00				
Steel	5	ton	200.00	1000.00				
Misc. iron	5	cwt	2.00	10.00				
Bolts	1	"	6.00	6.00				
Nails	2	"	6.00	12.00				
Screws	2	"	35.00	70.00				
Lumber framing	2	M	75.00	150.00				
Sheeting	1.5	"	80.00	120.00				
Millwork	Est.			75.00				
Roofing	12	"	3.00	36.00				
Paint	10	gal	3.00	30.00				
Plumbing	Est.			150.00				
Hardware	"			15.00				
Lights	5	ea	10.00	50.00				
Misc. equip.	Est.			75.00				
Sales tax	2			1.78				
M.S.E.	7			1.78				
Contingencies	10			2.98				
Total				3288.00			3288.00	

(Continued)

PACIFIC FRUIT EXPRESS COMPANY
RECEIVED
DEC 22 1944
OFFICE OF AUDITOR

PACIFIC FRUIT EXPRESS COMPANY
RECEIVED
DEC 12 1944
OFFICE OF AUDITOR

PACIFIC FRUIT EXPRESS COMPANY

SHEET 2 OF 2 SHEETS

WORK ORDER AUTHORITY—Detail of Estimated Expenditures

San Francisco, California

Engr. & Refrig.

DEPARTMENT

December 9, 1944

LOCATION: Tucson, Arizona

DESCRIPTION: Construct 20' x 35' temporary boarding house and lunch stand.

GENERAL MANAGER'S No. 0-681

DEPARTMENT No. E&R-1412

*DESCRIPTION	QUANTITY	UNIT	UNIT COST		LABOR	MATERIAL OR TRANSPORTATION CHARGES	TOTAL CHARGEABLE TO	
			LABOR	MATL.			INVESTMENT ACCOUNT	OPERATING EXPENSES
Contractor, Eng. & Supt.	Est.				400.00			
" Bond	"				42.00	60.00		
Comp. Ins.	"				100.00			
Contingencies	10	%			54.00	6.00		
Total					596.00	66.00		662.00
ACCT. 58 - MAINTENANCE ICING PLATFORM & MACHINERY.								
Future salvage chargeable to Material in Temporary Tracks, Structures, etc.								500.00
TOTAL	-	-	-	-				5554.00

TOTAL ESTIMATED EXPENDITURE

5554.00

ESTIMATE BY

DATE

193

APPROVED

APPROVED

*When labor or material is chargeable to both Investment Account and Operating Expenses show items separately.

PACIFIC FRUIT EXPRESS COMPANY
 RECEIVED
 DEC 12 1944
 OFFICE OF AUDITOR

PACIFIC FRUIT EXPRESS COMPANY
 RECEIVED
 DEC 22 1944
 OFFICE OF AUDITOR

Description	Quantity	Unit	Price	Amount	Balance	Total
Contractor, Eng. & Equip. Mat.				400.00		
Bond				48.00	00.00	
Comp. Ins.				100.00		
Contingencies				54.00	00.00	
Total				598.00	00.00	598.00

house and lunch stand.
 Constructed by temporary boarding

East. & Helzig.
 Tucson, Arizona

San Francisco, California

December 9

0-581

WAR-1-15

IN THE CHANCERY OF THE
 SUPERIOR COURT OF THE STATE OF CALIFORNIA
 IN AND FOR THE COUNTY OF SAN FRANCISCO

00.4552

00.4552